



# Premium Lift Systems

# **OPERATION AND PARTS MANUAL**





MODEL NUMBER : TL 1124
PART NUMBER : 1900-0021
SERIAL NUMBER :



Environmental Solutions Group 201 W. Main Street, Ste 300 Chattanooga, TN 37408 Bayne Customer Care: 800.535.2671

# **Cart Lifter General Operation Guidelines**

Always adhere to your company's safety guidelines when using this lifter. This includes wearing appropriate clothing and personal protective equipment, including reflective gear. Keep in mind that you are operating the lifter on public roads or alleys with moving traffic. Stay vigilant and watch out for vehicles and pedestrians.

The lifter should only be used for lifting ANSI-approved carts that are in good condition. It is not designed to be used as a step, to assist in lifting commercial containers, or to crush or break down items. Use with non-approved carts or misuse can result in serious injury or damage and will void the warranty.

Make sure the area around the lifter is free of personnel before operation. Always maintain a safe distance from the lifter to avoid pinch points that can cause serious injury.

Cart lifters can hang very low to the ground at certain points in the lift cycle. It is the operator's responsibility to move the lifter to a safe position, such as raising the lifter fully or placing the lifter in the storage position before driving. Lifters left hanging low risk bottoming out on the street, road, or alley. This can cause serious damage. Damages from bottoming out are not covered by the warranty.

It is the operator's responsibility to position the cart lifter safely before approaching any obstacles. Damages from collisions are not covered by the warranty.

# TABLE OF CONTENTS

		Page
I.	THINLINE <sup>®</sup> Safety	3
II.	THINLINE <sup>®</sup> Specifications	4
III.	THINLINE <sup>®</sup> Installation Instructions	6
IV.	THINLINE <sup>®</sup> Operation Instructions	13
V.	THINLINE <sup>®</sup> Diverter Valve Information	16
VI.	THINLINE <sup>®</sup> Maintenance Instructions	18
VII.	THINLINE <sup>®</sup> Actuator Assembly Instructions	19
VIII.	Trouble-shooting Chart	28
IX.	Appendix A	
	1. Unit Assembly Drawings	32
	2. Mounting Height Drawing	39
	3. Hydraulic Schematic Drawings	43
	4. Diverter Valve Drawings	45
	5. Hand Valve Drawings	
	6. Lubrication Drawing	49

# SAFETY (WI-0070-A) Bayne *THINLINE* <sup>®</sup> Premium Lift Systems

To prevent serious injury, death or equipment damage, read and understand this entire manual before installing, operating, repairing or adjusting your Bayne THINLINE <sup>®</sup> Premium Lift System. Those using and maintaining this equipment must be thoroughly trained and familiar with the product.

### I. Manual:

This manual must be kept in a location that is readily available for those who operate or maintain this equipment. Additional copies may be obtained from your local dealer or directly from Bayne THINLINE <sup>®</sup> Premium Lift Systems.

### II. Lockout/Tagout Procedures:

All applicable OSHA lockout/tagout regulations must be followed when working on this equipment. Failure to comply with these procedures can result in serious injury or death.

#### **III.** Safety Decals:

Safety decals attached to your Bayne THINLINE <sup>®</sup> Premium Lift System warn of hazards related to the use of this equipment. Operators must read and follow all safety instructions while using this equipment. If the safety decals are not clearly readable, new decals may be obtained from your local dealer or directly from Bayne THINLINE <sup>®</sup> Premium Lift Systems.

# SPECIFICATIONS (WI-0081-A) Bayne *THINLINE*<sup>®</sup> Premium Lift Systems

- A. Rotary Actuator rack and pinion style design.
  - Rack, pinion, and shaft bearings are constantly lubricated by the hydraulic oil for extended life.
  - Body and caps are made of high quality ductile iron.
  - Pinion output shaft and racks are made of high tensile alloy steel.
  - The rotary actuator provides smooth motion throughout the lift cycle, which results in longer cart life with virtually no cart damage or abuse.
- **B.** Arm bearings are made of a composite material which provides superior compression strength along with self-lubrication, thus eliminating the need to grease the arm bearings.
- **C.** The THINLINE<sup>®</sup> lift unit can measure as little as 5" thick from the front of the mainframe to the front of the faceplate depending on the types of arms used. This allows for easy dumping of large commercial containers without interference.
- **D.** The faceplate is normally at 45 degrees in the dump position and extends 13" to 15" from the back of the mainframe into the hopper or container opening. This places the cart or barrel 16" to 18" into the truck or container opening thus reducing any potential spillage of materials.
- **E.** Cycle times for safe, fast, efficient service.
  - 6 8 seconds for rear-load and side-load units
  - 8 10 seconds for units with 9" and 15" vertical lifts
  - 10 12 seconds for stationary, recycling, and double wide, and 24" vertical units
  - 15 30 seconds for 3300 series and 3300 series stationary units

*Note : Cycle time is controlled by flowrate, as flowrate increases, cycle times decrease.* 

# Warning : Never exceed the cycle times listed above. In order to avoid injury and maintain manufacturer's warranty never operate outside of these recommendations.

- F. Recommended flowrates are as follows:
  - 2 to 2 1/2 GPM for 1100 series units
  - 2 to 4 GPM for 2200 series units
  - 2 1/2 to 6 GPM for 3300 series units
- G. Hydraulic pressure requirements are as follows:
  - 2000 to 2500 PSI normal working pressure
  - 3000 PSI maximum pressure
- **H.** All lifters can be a bolt on type installation for easy, quick maintenance and less downtime.

- **I.** All parts are manufactured and kept in stock at Bayne Machine Works, Inc. for fast response to customer request.
- **J.** Two (2) year limited warranty from date of delivery on all units and models when properly maintained and operated within the recommended cycle time.

All lift units and parts are inspected by our Quality Control Department before shipment to insure that you always receive the highest quality available in the lift business. For more information, please contact us at 1/800/535-2671 or by fax at 1/864/458-7519.

# INSTALLATION INSTRUCTIONS (WI-0104-C) Bayne *THINLINE*<sup>®</sup> Premium Lift Systems

The following information is intended to be a <u>GENERAL GUIDE</u> to installing the **Bayne** *THINLINE*<sup>®</sup> lifter on a typical refuse truck. Before starting the installation, read these instructions completely. <u>ALWAYS</u> use the proper tools, lift devices, and personal protective equipment to prevent injury while performing the installation.

**<u>NOTE</u>**: If a **Bayne** *THINLINE* <sup>®</sup> Tap-In Kit was also acquired for this installation, refer to the installation instructions included in the Tap-In Kit manual for more detailed information.

## **IV.** Mounting lifter(s) on the truck :

- 1. The truck should be emptied and cleaned before any installation. The truck should be parked on a level solid surface, a concrete floor if possible.
- 2. All lights, tags, steps, etc. that will interfere with the installation should be removed and/or relocated.
- 3. Position the lifter(s) on the sill of the truck per *figure I-1* and mounting height drawing (*Appendix A*) and tack weld in place. If using an "S" unit for bolt on applications, tack weld the mounting plate in place and attach the lifter to the mounting plate using the 1/2" studs. (*tack weld only at this time so that adjustments can be made if necessary.*).





figure I-1

<b>Document Number:</b> 1900-0021	<b>Issue Date:</b> 04/22/13	Revision No: 006	Page: 6 of 49
-----------------------------------	-----------------------------	------------------	---------------

## V. Mounting hand valve(s) on the truck :

- 1. Choose and mark an acceptable location(s) on the side(s) of the truck to mount the hand valve assembly(s) (*figure I-2*).
- 2. Remove the mounting bracket(s) from the hand valve assembly(s) and weld to the truck.
- 3. After the weld has cooled, paint the mounting bracket(s) to match the truck color.
- 4. After the paint has dried, reassemble the hand valve assembly(s) on the mounting bracket(s).




## figure I-2

### VI. Mounting diverter valve on the truck :

- 1. Choose and mark an acceptable location to mount the diverter valve assembly. This location should be near the truck's main hydraulic pressure and tank lines on the same area of the truck where the lifter is mounted.
- 2. Weld diverter valve mounting bracket to the truck.
- 3. After the weld has cooled, paint the mounting bracket to match the truck color.
- 4. After the paint has dried, bolt the diverter valve to the mounting bracket using the 1/4" bolts, washers, and elastic lock nuts.

## VII. Making Hydraulic Connections :

Before attempting any hydraulic connections, turn the truck's engine off and release all hydraulic pressure from the system. Refer to the hydraulic layouts (figure I-3) and hydraulic schematics (Appendix A) while performing the following steps. Always clean & lubricate fitting threads before installation.



## Dual Lifter Installation

## figure I-3

- 1. Cut or disconnect truck's main hydraulic pressure line and install the diverter valve in series using the "IN" and "OUT" ports.
- 2. Connect the "T" port on the diverter valve to the truck's hydraulic tank line with an appropriate size line to handle the lifter system flow. (approximately 5 GPM max.)
- 3. Connect the "P1" port on the diverter valve to the "IN" port on the hand valve. *If installing dual lifters, connect the "P2" port on the diverter valve to the "IN" port on the other hand valve.*
- 4. Connect the "T1" port on the diverter valve to the "OUT" port on the hand valve. *If installing dual lifters, connect the "T2" port on the diverter valve to the "OUT" port on the other hand valve.*
- 5. Connect the "A" port on the hand valve(s) to the "UP" port of the rotary actuator(s).
- 6. Connect the "B" port of the hand valve(s) to the "DOWN" port of the rotary actuator(s).
- 7. Disassemble each hose clamp assembly and position weld plates where needed and weld in place.
- 8. After the weld has cooled, paint the weld plates to match the truck color.
- 9. After the paint has dried, reassemble the hose clamp assemblies around the hoses.

## VIII. Adjusting relief valve settings :

The diverter valve (1) (figure I-4) supplies the cart lifter hydraulic system with approximately 2 GPM of oil flow. This diverter valve is equipped with a lifter circuit relief valve (3) set at 2300 psi, to prevent the diverter valve from shutting down if a blockage occurs in the lifter circuit. There is also a relief valve (5) set at 1800 psi in the hand valve (2) to protect the lifter from excessive pressure. These relief valves are preset from the factory to operate properly on most trucks with a system pressure between 2300 and 2500 psi without any adjustment. However, if any adjustment is necessary, follow these instructions.

**WARNING :** Bayne equipment is rated for a maximum pressure of 3000 psi. Operation at pressures above 3000 psi may damage equipment and cause personal injury. In order to avoid injury and maintain manufacturer's warranty never operate above 3000 psi.





figure I-4

- 1. Determine the truck's system pressure setting.
- 2. Loosen lock nut (6) (*figure I-4*) from the hand valve relief valve(s) (5) and turn the adjustment screw(s) clockwise until it bottoms out.
- 3. Loosen the lock nut (4) (*figure I-4*) on the lifter circuit relief valve (3) and turn the adjustment screw clockwise until it bottoms out.
- 4. Start the truck's engine and engage the hydraulic system.
- 5. Operate the handle on the hand valve (2) (*figure I-4*) back and forth a few times to bleed all air from the lifter hydraulic system.
- 6. Turn the truck's engine off and release all hydraulic pressure from the system.
- 7. Install the 3000 psi hydraulic pressure gauge with the necessary adapter in the hydraulic line connected to the "IN" port of the hand valve as shown in figure I-5. *If installing dual lifters, install the hydraulic gauge at either one of the hand valves.*

Document Number: 1900-0021 Is	<b>ssue Date:</b> 04/22/13	Revision No: 006	Page: 10 of 49
-------------------------------	----------------------------	------------------	----------------





8. Start the truck's engine and engage the hydraulic system.

### 9. Setting the diverter valve lifter circuit relief valve :

- a) Have an assistant hold the handle on the hand valve (2) (*figure I-4*) (*with pressure gauge installed at the "IN" port*) in the "retract" position to show pressure on the gauge.
- b) Turn the pressure relief adjusting screw on the lifter circuit relief valve (3) counter-clockwise until the pressure reading on the gauge is either 100 psi less than the truck system pressure or 2300 psi, which ever is the lowest.
- c) Release the handle on the hand valve.

### 10. Setting the hand valve relief valve(s) :

- a) Hold a handle on the hand valve (2) (*figure I-4*) (*with pressure gauge installed at the "IN" port*) in the "retract" position to show pressure on the gauge.
- b) Turn the pressure relief adjusting screw on the hand valve relief valve (5) counter-clockwise until the pressure reading on the gauge is either 200 psi less than truck system pressure or 1800 psi, which ever is the lowest.
- c) Release the handle on the hand valve.
- d) Turn the truck's engine off and release all hydraulic pressure from the system.
- e) Remove the hydraulic pressure gauge from the hydraulic line connected to the "IN" port of the hand valve.
- f) For dual lifters, install the hydraulic pressure gauge in the "IN" port of the other hand valve as shown in figure I-5, start the truck's engine, engage the hydraulic system, and repeat step 10.
- 11. Reinstall the cap nut(s) ( 6 ) (*figure I-4*) on the hand valve relief valve(s) ( 5 ) to secure the correct pressure setting(s).
- 12. Tighten the lock nut ( 4 ) ( *figure I-4* ) on the lifter circuit relief valve ( 3 ) to secure the correct pressure setting.
- 13. The hydraulic circuit pressures are now set for optimum performance.

### VI. Final operation and mounting:

- 1. Start the truck's engine and engage the hydraulic system.
- 2. Place a cart on each lifter and operate to make sure there are no clearance problems and that the lifter engages the cart properly. Make any adjustments to the mounting position of the lifter(s) to ensure correct operation.
- 3. After locating an acceptable mounting position, complete the welding of the lifter(s) to the truck.

# OPERATION INSTRUCTIONS (WI-0124-A) Bayne *THINLINE*<sup>®</sup> Premium Lift Systems

The Bayne *THINLINE*<sup>®</sup> Premium Lift System is a high quality durable cart lifter built to meet your industry's requirements. To insure the safety of all operators of this equipment, please read this manual carefully before operating the lifter. *FAILURE TO COMPLY WITH INSTRUCTIONS COULD RESULT IN PERSONAL INJURY AND/OR PROPERTY DAMAGE.* 

The operating stages (figure O-1) in the cycle of the cart lifter are as follows:

- 1) **START** The cart to be dumped is placed on the lifter.
- 2) ACTUATOR DUMP The rotary actuator cycles to dump the contents of the cart into the box. During this cycle, the lower hooks automatically rotate to "lock" the cart to the lifter.
- 3) ACTUATOR REVERSE The rotary actuator reverses its cycle returning the cart to the start position. The lower hooks automatically retract to "unlock" the cart from the lifter.




figure O-1

# Warning: Exceeding the recommended cycle time on any lifter will void the manufacturer's warranty

The rotational motions of the cart lifter are controlled with the use of a hand valve. Moving the handle on the hand valve in one direction will cause the lifter to perform the actuator dump stage (figure O-1). Moving the handle in the opposite direction will cause the lifter to perform the actuator reverse stage.

Document Number: 1900-0021	<b>Issue Date:</b> 04/22/13	Revision No: 006	Page: 13 of 49
----------------------------	-----------------------------	------------------	----------------

## SAFETY ZONES

#### **Stand Clear Zone**

To prevent serious injury or death, operators and bystanders should remain outside the Stand Clear Zone (figure O-2) at all times during the operating cycle of the lifter. If at any point during the cycle persons enter this area, the operator most stop all motion of the lifter until the area is cleared.

#### **Dump Zone**

To prevent serious injury or death, operators and bystanders should remain outside the Dump Zone (figure O-2) at all times. If it becomes necessary to enter this area, all applicable OSHA lockout/tagout regulations must be followed.

#### **Operator Area**

To provide a clear, unobstructed view of both the Stand Clear Zone and Dump Zone, operators should remain within the Operator Area (figure O-2) at all times during the operating cycle of the lifter.





figure O-2

## LOWER HOOK ADJUSTMENT

Check the distance (A) (figure O-3) between the saddle and lower hooks when the lifter faceplate is in the *FULL DUMP* position. Maintain this dimension at approximately 14 1/4" for the proper "locking" of the cart to the lifter. To adjust the setting, loosen the jam nuts (1) on the spherical rod ends (2). Remove the bolts (3) that hold the rod ends to the lower hooks (4). Screw the rod ends in or out as required to obtain the correct dimension at (A). Replace the bolts (3) and tighten the jam nuts (1).



#### figure O-3

**CAUTION:** The distance in figure 0-3 is an arbitrary figure based on information furnished by cart manufacturers. It is the responsibility of the owner / operator of this equipment to adjust these dimensions to be compatible with his specific application.

## 6091/6092-0700 DIVERTER VALVE OPERATION AND INSTALLATION INFORMATION (WI-0026) Bayne *THINLINE*<sup>®</sup> Premium Lift Systems

The Bayne diverter valve establishes priority flow to the lifter circuit "P1" and "P2" ports and bypasses oil to the "OUT" port, which typically supplies flow to the remainder of the truck's hydraulic circuit. This bypass occurs only after the lifter circuit is satisfied. The priority flow is controlled by the flow regulator cartridge (FR1) (and FR2 in dual applications) in combination with the differential pressure sensing valve (DPS). This allows the valve to maintain constant flow regardless of changes in load pressure or volume flow rate. Since both the lifter circuit and bypass flow can be utilized in the operation of the truck regardless of which pressure is greater, a single pump can be used to supply two circuits or operations.

The lifter circuit flow is regulated and maintained by the flow regulator cartridge (FR1) (and FR2 in dual applications). The differential pressure sensing valve (DPS), rated for 75 gpm of flow and 3000 psi of pressure, is operated by an internal spring and dampening orifice (OR) which establishes a pressure drop across the block sufficient to ensure the correct operation of the flow regulator (FR1). For a dual diverter valve, a second flow regulator cartridge (FR2) is installed in the "FR2" cavity and a shuttle valve (DSV) is installed in place of the SAE plug in the "DSV" cavity. Once the pressure drop is established, a precision metered flow is provided to the tipper circuit(s) with additional flow being bypassed to the "OUT" port.

The operation of the diverter valve does not require the use of a tank line to be run to the "T" port. However, the efficiency of the block will be significantly increased if a tank line is installed. The logic circuit of the block will manage the flow of oil returning from the tipper circuit to ensure optimum performance. This is primarily controlled with the sequence valve (PSV) which is factory set and should not be adjusted. All oil returning from the tipper circuit will normally be regenerated into the outgoing flow to ensure that the downstream functions are not slowed in any way. When the downstream backpressure rises to a predetermined pressure, the block will redirect the flow to the "T" port to increase the overall efficiency of the block and reduce the pressure drop through the block. If the "T" port is connected to a tank line, the oil will be dumped through the block at a lower pressure. This allows downstream functions to operate at the highest possible pressure when pressure is being required. If the "T" port is blocked, the oil will be redirected back into the outgoing flow through the check valve (CV).

A relief circuit for the tipper function is controlled by a relief valve (RV), which is preset to 2300 psi. This can be adjusted to limit pressure to the tipper(s). This relief valve is more efficient than the relief in the hand valve and will operate with less noise. It is recommended that it be adjusted to relieve before the hand valve relief. It may also be used to limit the weight the lifter can dump. This may be beneficial in avoiding damage to cans resulting from overloading. This should be the only adjustment that the block may require. Any other adjustments should only be made after close consultation with Bayne's Engineering Department to ensure proper operation.

### **POSSIBLE PROBLEMS**

- 1. The most common cause of valve failure is dirty oil. If debris becomes lodged in the cartridge valves they will malfunction. Recommended filtration level is between 15 and 25 microns. Many systems filter the oil on the return side. This does not guarantee clean oil going into the system. It is important to ensure that the tank vent filtration element is properly maintained as well. Very small contaminants may not cause the valve to stop functioning, but can cause "stiction" in the cartridges between the body and the moving spool. This can cause improper operation. A slow moving tipper is most likely the result of contamination in the flow regulator cartridge. A pulsating noise may be the result of contamination in the differential pressure sensing valve causing it to stick. If any valve malfunctions, remove and thoroughly clean the valve, being extremely careful not to score or abrade the "o" ring seals or moving parts of the valve. Be sure that the spool moves freely in the valve body.
- 2. The flow regulator cartridges (FR1 and FR2) are designed to operate at a designated pressure of 80 psi. This means that in order for the valve to function properly, a minimum of 80 psi is required from the supply line through the "IN" port of the valve. This can present a problem on trucks with a dry valve pump system. Normally in the dry (off) mode of the pump, a flow of approximately 2 gpm at 20 psi is required to circulate through the open center system of the truck. This is for pump lubrication in the off mode. When the diverter valve is placed in the main pressure line of the truck, a blockage occurs because of the differential pressure sensing valve needing 80 psi to initially open and allow the flow regulators function. The path of the lubrication oil is therefore stopped because the valve does not open. When the oil is blocked, the pump will rotate and cavitate in the lubricating oil, causing heat to build up over an extended period of time, possibly leading to premature pump failure. To prevent this problem from occurring, a "bleed line" circuit needs be installed on the truck to allow passage of the lubricating oil back to tank.
- 3. On front load residential truck applications, several considerations need to be noted. The Bayne hand valve is an open center valve that allows for the lifter circuit to maintain flow through the hand valve and back to the diverter valve when the lifter is not being operated. If flow is not maintained through the hand valve, the oil will constantly be relieving over the lifter circuit relief valve (RV) in the diverter valve, which can cause an increase in operating temperature. Certain front load box designs allow for the hand valve to be located on the arms of the truck which keeps the hand valve in the lifter circuit at all times to maintain flow. Most problems occur with applications where the hand valve is located on the box itself. In this situation, when the operator disconnects the hydraulic lines to the box, a blocked condition occurs in the lifter circuit. To prevent this problem, the pump must be turned off prior to disconnecting the box hydraulic lines. Once the lines have been disconnected from the box, it is necessary to connect the two lines for the hand valve to each other to functionally complete the lifter circuit. It is recommended that male and female quick disconnects be used opposite each other on the truck to provide an uninterrupted circuit. Once the lines have been connected and the circuit continued, the pump could then be turned on to continue operations.

# MAINTENANCE INSTRUCTIONS (WI-0140-A) Bayne *THINLINE*<sup>®</sup> Premium Lift Systems

## NOTE:

THE MOST COMMON CAUSE OF HYDRAULIC COMPONENT FAILURE IS CONTAMINATION OF THE HYDRAULIC FLUID (WATER, CHIPS, DIRT, ETC.) THE Bayne *THINLINE*<sup>®</sup> LIFT SYSTEM COMES CLEAN FROM THE FACTORY. IF REMOVED, BE SURE THE HOSES, CYLINDER AND FITTINGS ARE CLEAN BEFORE RE-INSTALLING THEM ON THE UNIT.

Inspect your cart lifter on a weekly basis for loose bolts, fittings, oil leaks, etc. Tighten loose hardware as necessary and replace necessary seals to repair oil leaks.

In order to maintain warranty and for preventive maintenance, grease all points weekly with a good multi-purpose grease at points shown in the lubrication drawing (*APPENDIX A*).

Document Number: 1900-0021	<b>Issue Date:</b> 04/22/13	Revision No: 006	Page: 18 of 49
----------------------------	-----------------------------	------------------	----------------

# **BAYNE** PREMIUM LIFT SYSTEMS

## ASSEMBLY INSTRUCTIONS 1100 SERIES ROLLER BEARING ACTUATOR PART NUMBER 1120-1025 (WI-1109-E)

# LICENSED UNDER ONE OR MORE OF THE FOLLOWING U.S. PATENTS: 4,773,812 1,327,765 5,308,211 5,333,984

## **READ INSTRUCTIONS COMPLETELY BEFORE STARTING ASSEMBLY.**

Before starting the assembly of the Rotary Actuator, refer to the exploded parts drawing and parts list (fig. A-13 found at the end of these instructions) to familiarize yourself with the individual components. Prepare a clean surface, in an area free of blowing dust and contaminants in which to assemble the Rotary Actuator. Be sure that all parts are thoroughly clean and dry before starting assembly.

**<u>NOTE</u>**: All torque values given apply to clean dry threads only. Follow these directions closely when repairing the Rotary Actuator.

Install the piston seal load ring (13) (fig. A-1) in the small groove on the head of the actuator rack (2). Place the "square" piston seal (17) over the load ring (13) in the same small groove (a small "*blunt*" flathead screwdriver may be used, taking care not to scratch or damage the seal). Install the wear ring (18) in the large groove on the head of the rack. Using a ring compressor, firmly seat the rings on the rack before setting it aside, this will help to reverse the effects of any stretching of the rings that occurred during installation. Repeat this procedure for the other rack.




figure A-1

2. Install the tube seal (12) (fig. A-2) and "square" tube seal backup (16) on each end of the actuator tubes (3) (fig. A-13). Be sure that the "square" tube seal backup ring is toward the inside of the tubes at both ends as shown. Press all rings firmly into the grooves. Repeat this procedure for the other tube.




figure A-2

3. Thoroughly clean the pinion shaft (1) (fig. A-3) and inner races (10) with a mild solvent and dry completely. Spray the inner race contact area (shown in figure A-3) at each end of the pinion shaft and the inside diameter of the inner race thoroughly with *LOCTITE* 7649 N PRIMER. Apply LOCTITE RETAINING COMPOUND 609 around the pinion shaft at contact area and the inside diameter of the inner races. Slide the inner races (10) on the pinion shaft (radius end first as shown in figure A-3) until the races seat against the gear teeth. After the races seat against the gear teeth, twist the races on the pinion 360° to spread the retaining compound evenly. Wipe off any excess retaining compound.




figure A-3

4. Place the actuator body (7) (fig. A-4) on the edge of the table, mounting flanges closest to the assembler with the counter-bores facing up. Insert the pinion shaft (1) through the bore on either side of the actuator body with the key ways facing back toward the mounting flanges and up away from the table with the center line of the key ways pointing toward the center of the tapped hole shown in figure A-4. Center the pinion in the actuator body.




figure A-4

5. Coat the head portion of the racks (2) (fig. A-13) with STP Oil Treatment. Install the racks, head portion up with the teeth facing the flanges of the actuator body, into the dual set of bores in the body. Simultaneously slide the racks into the bores so that the racks mesh with the pinion in the same position. Rotate the pinion shaft to engage the racks into the pinion.




figure A-5

Document Number: 1900-0021	<b>Issue Date:</b> 04/22/13	Revision No: 006	Page: 21 of 49
----------------------------	-----------------------------	------------------	----------------

6. Check the position of the racks in the pinion by making sure both racks seat against the actuator body at the same time and also when the racks are seated against the body, the key ways on the pinion shaft should be facing down toward the table and very slightly back toward the mounting flanges on the actuator body as shown in figure A-6.




figure A-6

7. Coat one end of the actuator tubes (3) (fig. A-13) around the seal area with STP Oil Treatment as shown in figure A-7. Using a rubber mallet, drive the coated end of the tube onto the exposed rack until the tube end seats in the actuator body, making sure that the seals remain in place as the tube enters the counter-bore. Repeat this procedure for the other side.




figure A-7

<b>Document Number:</b> 1900-0021 <b>Issue Date:</b> 04/22/13	Revision No: 006	Page: 22 of 49
---	------------------	----------------

- 8. Install the six tie rod studs (6) (fig. A-13) by screwing the short threaded end into the actuator body. Hand tighten only at this time (the torque needed will be applied later in the procedure).
- 9. Place the tube cap (4) (fig. A-13) on the table. Coat the sides of the two bores in the tube cap with STP Oil Treatment. Install the cap over the tubes and rod studs with the oil port positioned to the left as shown in figure A-13. Using a rubber mallet, tap the tube cap over the tubes until the tubes seat in the cap, making sure that the seals remain in place.
- 10. Place the tube mounting bracket (30) (fig. A-13) over the two end rod studs opposite the oil port in the tube cap as shown in figure A-13.
- 11. Install the hex nuts (23) (fig. A-13) and lock washers (24) on the tie rod studs. Torque the nuts to 50 ft-lb. in the sequence shown in figure A-8.





figure A-8

12. Place the rack cap (5) (fig. A-13) bore side up on the table and coat the edge of each bore with STP Oil Treatment. Install the rack cap seals (14) (fig. A-9) in the rack cap.



13. Reposition the actuator on the table mounting flanges down, and the lower tubes facing away from the assembler. Rotate the pinion shaft to allow 1" of the rack to protrude from the top of the actuator body. Install the rack cap with the oil port positioned to the left hand side of the actuator opposite the bottom oil port located in the tube cap as shown in figure A-13. Attach the rack cap to the actuator body using the socket head bolts (22) (fig. A-13) and lock washers (26). Torque the bolts to 90 ft-lb. in the sequence shown in figure A-10.




figure A-10

14. Reposition the actuator so that the pinion shaft can be rotated with no obstacles. Rotate the pinion shaft to ensure that the racks move freely. Also make sure that the key ways point perfectly straight "up" toward the rack cap and "down" toward the tube cap at each end of the 180° stroke. If the assembly does not perform all of these functions correctly, it must be disassembled, cleaned, and reassembled.

- 15. Re-center the actuator pinion in the actuator body by tapping on one end of the shaft with a rubber mallet. Install the roller bearing (9) (fig. A-13), over the pinion shaft and inner race, and into the actuator body. Repeat this procedure for the other bearing.
- 16. Thoroughly clean the bearing caps (8) (fig. A-11) with a mild solvent and lubricate all seal grooves with STP oil treatment. Place the bearing caps (8) on the table (mounting surface down) and install the wiper ring (19) in the outside groove using a rubber mallet or small press. (Avoid using tools that may damage seals or scratch bearing cap or bearing surfaces.) Turn the bearing cap (8) over. Collapse the pinion seal (20) and carefully work it into the groove. Use fingers to carefully press the seal completely into the groove as shown in figure A-11. Be careful not to score or scratch the sealing surface during the installation. Install the bearing cap seal (15) and thrust washer (32) into their respective grooves on the bearing cap mounting surface as shown in figure A-11.
- 17. Coat the bearing cap seal area and pinion seal area shown in figure A-11 lightly with STP Oil Treatment.




figure A-11

18. Wrap masking tape or electrical tape around the pinion to cover the edges at the keyway. Slide the bearing cap assembly over the pinion shaft with the bearing cap seal facing toward the actuator body and the flat surface of the flange shown in figure A-12 facing toward the actuator mounting flanges. Press against the bearing cap until the shoulder seats against the actuator body, making sure that the seals remain in place. Install the bearing cap bolts (21) (fig. A-13) and lock washers (25). Hand tighten only at this time. Repeat this procedure for other bearing cap. 19. After both bearing caps have been installed, torque all bearing cap bolts to 30 ft-lb. in the sequence shown in figure A-12.




figure A-12

- 20. Install the 90° fitting (27) (fig. A-13) into the oil port on the side of the rack cap (5). Hand tighten only at this time.
- 21. Install the 45° bulk-head fitting (31) (fig. A-13) up through the hole in the tube mounting bracket (30) bolted to the tube cap as shown in figure A-13. The 45° end must be pointing down away from the rack cap (5) and back toward the mounting flanges on the actuator body. Hand tighten only at this time.
- 22. Install the rack cap extension tube assembly (29) (fig. A-13) between the 90° fitting in the rack cap and the 45° fitting in the tube mounting bracket as shown in figure A-13. Tighten all connections.
- 23. Install the orifice plug (11) (fig. A-13) into the oil port on the side of the tube cap (4), and install the 90° fitting (27) into the oil port over the orifice plug as shown in figure A-13. Turn the fitting so that it points down away from the rack cap (5) and back toward the mounting flanges on the actuator body and tighten.
- 24. Install the cap nuts (28) (fig. A-13) onto the open fittings to prevent contamination of the unit until the hoses are installed.
- 25. Install the actuator cover plate (33) (fig. A-13) onto the rack cap (5) using the cover plate bolts (34). Be sure to use *LOCTITE THREADLOCKER 242* on the cover plate bolts.

# **ACTUATOR ASSEMBLY**




figure A-13

# TROUBLE-SHOOTING CHART (WI-0046)

SYMPTOM	POSSIBLE CAUSES	CORRECTIVE ACTION
Lifter operation very erratic.	1. Air trapped in system.	<ol> <li>Bleed all air from lifter hydraulic system.</li> </ol>
	2. Low oil level.	2. Add oil to system.
Cart lifter will not pick up carts.	1. Cart overweight.	1. Reduce loaded weight of cart.
	2. Lifter system hydraulic pressure too low.	2. Check and adjust pressure relief on hand valve and lifter circuit relief in diverter valve.
	3. Truck system hydraulic pressure too low.	3. Check and adjust pressure on truck system relief and full system relief in diverter valve.
	4. Faulty hand valve.	4. Replace hand valve.
Lifter operates extremely slow.	1. Engine idle too low.	1. Adjust engine idle.
510w.	2. Faulty hand valve.	2. Replace hand valve.
	3. Faulty truck hydraulic pump.	3. Consult truck maintenance manual.
	4. Trash in diverter valve.	4. Remove orifice from diverter valve body and clean thoroughly.
	5. Orifice in diverter valve is too small.	5. Remove orifice from diverter valve body and increase diameter.
Lifter operates under	1. Engine idle too high.	1. Adjust engine idle.
recommended cycle time.	<ol> <li>Orifice in diverter valve is too large.</li> </ol>	2. Remove orifice from diverter valve body and replace with a smaller diameter.

# TROUBLE-SHOOTING CHART (WI-0046)

SYMPTOM	POSSIBLE CAUSES	CORRECTIVE ACTION
Hydraulic components down stream of diverter valve not operating or operating extremely slow.	1. Truck system hydraulic pressure too low.	<ol> <li>Check and adjust pressure on truck system relief and full system relief in diverter valve.</li> </ol>
	2. Faulty full system relief valve cartridge in diverter valve.	2. Replace full system relief valve cartridge in diverter valve.
	3. Faulty truck system relief valve.	3. Consult truck maintenance manual.
	4. System flow is being restricted.	4. Ensure there is proper flow throughout the hydraulic system. Remove any restrictions.
	5. Trash in flow regulator cartridge.	5. Remove flow regulator cartridge from diverter valve body and clean thoroughly.
Diverter valve leaking oil around cartridges.	1. Worn or damaged seals on cartridge valves.	<ol> <li>Install diverter valve seal kit.</li> </ol>
Hand valve lever sticks in up or down position.	1. Worn or broken spring center device.	1. Install spring center kit.
	2. Trash in or around hand valve shift spool.	2. Disassemble and clean spool and housing.
	3. Pressure (IN) and tank (OUT) ports are hooked up backwards.	3. Make sure all hoses are plumbed according to the hydraulic schematic.
Hand valve leaking oil around shift spool.	1. Worn or damaged seals.	<ol> <li>Install hand valve seal kit.</li> </ol>
	2. Worn spool.	2. Replace hand valve.


# TROUBLE-SHOOTING CHART (WI-0046)


SYMPTOM	POSSIBLE CAUSES	CORRECTIVE ACTION
Actuator leaking oil around pinion shaft.	1. Worn pinion shaft seals.	1. Install pinion seal kit.
Actuator leaking oil around piston tubes or rack cap.	1. Worn seals in actuator.	1. Install actuator seal kit.
Lower hook connecting rods frequently breaking or bending.	1. Saddle to hook dimension out of adjustment.	<ol> <li>Adjust saddle to hook dimension as described in the Operation Instructions of this manual.</li> </ol>
	2. Bars on carts are not standard spread dimensions.	2. Re-adjust saddle to hook dimension for these carts.
Lifter looses cart when dumping.	<ol> <li>Saddle to hook dimension out of adjustment.</li> </ol>	<ol> <li>Adjust saddle to hook dimension as described in the Operation Instructions of this manual.</li> </ol>
	2. Lift bars on cart are bent or spread apart.	2. Replace cart or install new bars.
Lift bars on cart are being spread apart or damaged.	<ol> <li>Saddle to hook dimension out of adjustment.</li> </ol>	<ol> <li>Adjust saddle to hook dimension as described in the Operation Instructions of this manual.</li> </ol>


# **APPENDIX A** Assembly drawings and part numbers

Document Number: 1900-0021	<b>Issue Date:</b> 04/22/13	Revision No: 006	Page: 31 of 49
----------------------------	-----------------------------	------------------	----------------


QTΥ	~	-		 	പ	വ	പ	-	-	- 0	u (	υ <b>-</b>	1 ·		1		-1		4	N		1	N	4	р 1	വ	m	16	Р1 С1	N	പ	വ	00	00	4	12			rev. F	Ę	μ
ITEM PART ND. DESCRIPTIDN	1 1120-1025 1100 SERIES RULLER BEARING ACTUATUR	21" STANDADD MATNEDAME	2024-1201 24"	2024-120524" IURQUE ARM (L.H.)		6  7500-0117 TDRQUE ARM WASHER	7 7 7300-0410 KEY (1/4" × 1 3/16" LG.)	8 2024-1301 24" IDI FR ARM (R.H.)	2024-1305 24"		CUUUTIOGO LELWER INCER BEARING	II /2UUU-I333 UPPER IULER BEARING ASSEMBLY	VINUTIVIUM I VINUTVI	2000-1500	14 2000-3900 SADDLE	15   5000-0010   WARNING LABEL	16   5000-0060   NDTICE LABEL	17 7500-0070 MDDEL/SERIAL NAME PLATE	SCREW	19 2000-1400 HDDK	20 2000-1450 HODK LINKAGE	21 2000-1470 HDDK SHAFT	22 7500-0006 RDD END SPACER	23 7202-0800 SPHERICAL RDD END	24 9001-0608 3/8-16 × 1" H.H.C.S.	25 9002-0608 3/8-24 × 1″ H.H.C.S.	26 9401-0600 3/8-16 HEX NUT	27 9600-0500 5/16" FLAT WASHER	-	9001-0808 1/2-13 × 1" H.H.C.S.	9001-0812 1/2-13 × 1 1	9002-0816	32 9402-0800/1/2-20 HEX NUT	33 9502-0800 1/2-20 HALF NUT	34 9600-0800 1/2" FLAT WASHER	35 9700-0800 1/2* LOCK WASHER			serville, S.C. It MUST NOT be copied or lent SCALE: SHEET OF ion of order to the purchasing department. $1{=}2$ $1$ $3$	CHK'D BY: DATE: TL 1124 DWG. NO:	
QTY	D STUD 4	4 2 1		ru	<u>a</u>	0	1	-																															the property of BAYNE MACHINE WORKS, INC., Gre be promptly returned with tender and/or complet	DIED: DRAWN BY: DATE: CHR	L
PART ND. DESCRIPTION	9902-081411/2-20 × 1 3/4" THRFADED	1/2-20 / 2% THPE/	<  >	1/2-13 × 1"	9201-1010 5/8-11 × 1 1/4" B.H.C.S.	9600–1000 5/8″ FLAT WASHER	5000-0015 BAYNE LOGO LABEL															LINE INDICATES ITEM NO.	LINDICALEV & T.	3LUE> P/N 7500-0055	STENERS UNLESS		ΈΔ> Ρ/Ν 7500-0057.			05/13/10 CTT C1565	· 11/11/02 CTT TUT C1317	05/30/01 TBR ANR C1302	λ	04/10/00 ANR RTM C1251			B ANR RTM	DATE REY BY BY NO.	This drawing is private and confidential communication and the property of BAYNE MACHINE WORKS, INC., Greenville, S.C. It MUST NOT be copied or lent without consent of BAYNE MACHINE WORKS, INC., and must be promptly returned with tender and/or completion of order to the purchasing department.	DRRS AND TOLERANCES IF NOT NOTED:	864.288.3877 0/0 ±1732
ITEM PA					40 92	41 96	42 500													NUTE		1 (XX) FIGURE ABOVE L	XX I LUNKE BELLUM	2, USE LOCTITE #242 (I	DN ALL THREADED FASTENERS UNLESS	UTHERWISE NUTED,	3. USE LOCTITE #271 (RED) P/N 7500-0057.			E   5000-0060 WAS 5000-0020 ADDED 5000-0015	D UPDATED 2000-1101 PICTORIALLY	C 7500-0171 QTY, 4 WAS 2 9400-0500 VAS 9400-0500	UPDATED 2000-1335 PICTORIALL	B 2000-1230 WAS 2000-1220	2000-1335 MAS 2000-1325	AUUEU /500-01/1 & 9600-0600 REMOVED 7002-0400		LET, REVISIONS	CONFIDENTIAL This dr without	BAINNE NUARINE DUDRICS	ROAD - CR










**Document Number:** 1900-0021 **Issue Date:** 04/22/13 **Revision No:** 006 **Page:** 35 of 49







**Document Number:** 1900-0021 **Issue Date:** 04/22/13 **Revision No:** 006 **Page:** 38 of 49





		ш. Т.		1				ш I		1				<u> </u>		7	ŧ			o						<u></u>	1		<b>RC</b> 288.3877		OF A	t KEV	I
۲	"L" DIM.		20°	° Cu	R	°55	00	<u>्</u> य	00	°C3	60	° L J	60		47°		۰۷	47	49°	era د	20	° C L	76	0 0 1	ŝ	0 0 1	ß		<b>છ</b> ે.		SHEET	00027	1
_	"K" DIM.		80 3/4"	0.7 <sup>11</sup>	10	"1/1 00	8U 1/4	06 E/0"	00 2/0	"0/C 0/	10.010	OFI	00		89 1/8"		"1/1 30	30 I/4	89 1/4"	"0/ <u>7</u> 00	00 / /0	101 10	90 1/0	07 E /01	0/0 /0	"0/ 1 VU	34 1/0		CHINE WORL - GREENVILLE, SC 2905	FICATIONS	SCALE		-
2	.'.' DIM.		34 1/8"	"2" 7	4/1 1/4	"0/CCC	32 3/8	"1/000	30 3/4	20 E /o"	0/C 67	1177 90	4/1 OC		43 1/4"		""" "	47 1/4	42 7/8"	"F/C FF	4   0/4	Ō	40	"0, 1 00	211 60	161	40		<b>BA WNE MACHINE</b> 910 FORK SHOALS ROAD - GREENVILL	TL SERIES SPECIFICATIONS	DATE 4 0 100 10000	DATE	10
_	"H" DIM.		38 3/4"	20 1 D''	7/1 00	10/ F C F	43 1/8	101	411/0	10/2 7 7	44 //0	10/0 07	0/0 04		38 1/2"		10/1 20	0/1 00	38 3/4"	"C7	5		40 3/4	4 E 4 /0"	0/1 C+		4/- C4			F	- E	CHECKED BY	_
3	.G" DIM.		18 7/8"	1 C E 10"	0/0 01	"0/ F FC	Z1 1/0	"0/ F O F	19 I/Q	20 3/4"		19 1/8"			19 5/8"		"14 7 7	1/ 1/4	19 1/8"		<del>7</del> 7   <del>14</del>		Q/I.07	10" 10"	0/0 77	" <i>17 0 00</i>	4/C U∠	NISE SPECIFIED	ARE IN INCHES RANCES: AL ±1/32 E DECIMAL ±015	THREE PLACE DECIMAL ±005 ANGLLAR TOLERANCES: NACHINED ±0.25 DEG BEND ±1.00 DEG		WEIGHT	ę
	"F" DIM.		5/8"	Ę	_	1 7/0"	1 //0	"0/ F C	Q/1 7	= <sup>2</sup> 7 0	2 1/4	1177 0	Z 1/4		1 1/4"		"C/ F F	7/1 1	1 1/8"	"0 <sup>7</sup> U	0/0 7	20 1 0	Q/ 7	Ę	n	Ę	n	UNLESS OTHER	DIMENSIONS LINEAR TOLE FRACTION/ TWO PLACI	THREE PLA ANGULAR TO MACHINED BEND ±1.0			
4	"E" DIM.		41 3/4"	" F O I F	4/C C4	"0/ F C F	4.3 1/8	"""	40 3/4	10/ C V	421/0	1070 01	40 0/0		49 3/4"		E2 7/0"	0// 00	49 3/4"	E 4 1,01	0/1 10		Q// +C	÷ U	0	E 4 E /0"	0/0 +0	CONFIDENTIAL	NTAINED IN THIS E PROPERTY OF KS. INC. AND IS	rime. It must Sed He interest of Ks inc			4
	"D" DIM.		40"	2 7 1 2 1 2	2/1 C4	"0/ Z .0.V	40 //0	"0/ C	44 3/0	"F1 F O F	40 1/4		4,0 0,4		45 3/8"		10/ L 0 V	40 //0	45 3/4"	101 7 7 7	40 1/0		49 0/Q	4 E 4 201	7/1 C4	"O	τ γ	CONFIL	HE INFORMATION CC RAWING IS THE SOLE AYNE MACHINE WOR	RECALLABLE AT ANY TIME. IT MUST NOT BE COPIED OR USED DETRIMENTALLY TO THE INTEREST OF BAYNE MACHINE WORKS INC.	MATERIAL	QTY FINISH	_
Þ	"C" DIM.		16 1/8"	4 C 4 101	0/1 01	"V" - U		"V" - V	10 1/4	4 C 4 101	0/1 01	101	0/1 01		16 1/8"		101 4 24	0/1 01	16 1/4"	171 7 7	10 1/4		10 1/4	4 C 4 101	0/1 01	101	0/1 01				-		
ъ	"B" DIM.	i		ř	~	"O, 4 C 4		"0/ F C F	Q/I 71	- 7	<u>5</u>	Ē	<u>5</u>		7"		14	,	8 1/2"		7/1 7/1		Q/I 71	"0/ C C T	0/0 01	- F ( 7	4/1 C1						5
_	"A" DIM.		38	41 1/2"			30 3/0	14 7/0"	41//0	38"		41 1/2"			42"		15 4 101	7/1 C4	42 3/8"		42 3/0		Q// C+		0/1 74	1 E E /0"	40 0/0						_
9	PART #	1900-0017	1900-3017	1900-0250	1900-0228	1900-0033	1900-0237	1900-0170	1900-0171	1900-0120	1900-0190	1900-0172	1900-0173	1900-0019	1900-3019	1900-0023	1900-0252	1900-0257	1900-0166	1900-0119	1900-0138	1900-0167	1900-0168	1900-0035	1900-0039	1900-0169	1900-0174						9
	MODEL NUMBER	TL 1116	TL 1116 F.L.B.	TL 1116 (TOP HOLES)	TL 2216 (TOP HOLES) **	TL 1116-2524	TL 2216-2524 **	TL 1116-2524 (TOP HOLES)	TL 2216-2524 (TOP HOLES) **	TL 1116-2526	TL 2216-2526 **	TL 1116-2526 (TOP HOLES)	TL 2216-2526 (TOP HOLES) **	TL 1120	TL 1120 F.L.B.	TL 2220 **	TL 1120 (TOP HOLES)	TL 2220 (TOP HOLES) **	TL 1120 (1/4" OFFSET IDLER)	TL 1120-2524	TL 2220-2524 **	TL 1120-2524 (TOP HOLES)	TL 2220-2524 (TOP HOLES) **	TL 1120-2526	TL 2220-2526 **	TL 1120-2526 (TOP HOLES)	TL 2220-2526 (TOP HOLES) **						
8			Ĩ	TL	ЦГ	TL		TL.	ТГ	TL	TL	TL			TL		цг. Д	ТГ			TL	ТГ		TL		B TL	TL:				A		œ


	* 1040	MIC	MIC ::0:				MIC	MIC				MC
	1900-0021											
	1901-0021											
TL 1124 (.059" ORIFICE)	1900-0232	Ĩ	Ē				11 C/ L					
TL 1124 (3/8" KEY)	1900-0176	- 40		16 1/8"	"90 1/8"	"8/G / G	1 5/8"		38 1/4"	"8/ <i>1</i> / 6	97 3/8"	45,
TL 1124 (3/8" KEY) (.059" ORIFICE)	1900-0276											
	1900-0025											
TL 1124 (TOP HOLES)	1900-0177											
TL 1124 (TOP HOLES) **	1900-0254	"C/ Y OF	Ĩ	10 4 (Oli	101	10 1 D 141	110/ Z	10/10/	" <i>V</i> (0 10	E 7 7 (0)		1 00
TL 1124 (TOP HOLES) (3/8" KEY)	1900-0221	- 49 112	<u>_</u>	_0/I 0I		013/4					103 1/4	.04
TL 2224 (TOP HOLES) **	1900-0259											
TL 1124 (1/4" OFFSET IDLER)	1900-0236	46 1/2"	8 1/2"	16 1/4"	50 1/2"	57 5/8"	1 1/2"	19 1/2"	38 1/2"	51 1/2"	97 1/2"	48°
TL 1124 (1/2" OFFSET IDLER)	1900-0240	46 7/8"	9 3/4"	16 1/2"	51"	57 1/2"	1 3/8"	19"	38 3/4"	51 1/8"	97 3/4"	49°
	1900-0137											
	1901-0022	46"	11"	16 1/8"	50 1/8"	58 1/4"	2 1/2"	22 1/4"	43"	49 3/8"	96 1/2"	52°
	1900-0139											
TL 1124-2524 (TOP HOLES)	1900-0178	"01101	- - -	16.1/8"	53 5/8"	ео 1 <i>1</i> л"	3 1/8"	"8/1 00	"10 2/1	<u>с</u> с/8"	"102 2/1"	ξο°
TL 2224-2524 (TOP HOLES) **	6210-0061	43 112	=	0/1 01	0/0 00	02 1/4	0/1 0	0/1 0/2	410 014	0/0 00	4/C 701	20
	1900-0162											
	1900-0037	46"	13"	16 1/8"	50 1/2"	58 3/4"	3"	23 3/8"	45 1/8"	48 3/8"	96 1/8"	55°
	1900-0041											
TL 1124-2526 (TOP HOLES)	1900-0184	10, F 0 F	Ē	101 7 97	Ę,		10/00					o L L
TL 2224-2526 (TOP HOLES) **	1900-0185	211 64	<u>c</u>	0/1 01	5	0/6 70	0/C C	0/0 1 7	0/1 C+	4/0 40	0/0 701	ĉ
						CONFIDENTIAL RMATION CONTAINED IN THIS		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES LINEAR TOLERANCES:		NF MAC	HINF W	RKS MC
					DRAWING IS THE SOI BAYNE MACHINE WO RECALLABLE AT ANY	LE PROPERTY OF RKS, INC. AND IS TIME. IT MUST		NAL ±1/32 VCE DECIMAL ±015 LACE DECIMAL ±005		SHOALS ROAD -	910 FORK SHOALS ROAD - GREENVILLE, SC 29805 - 86	
					NOT BE COPIED ORI DETRIMENTALLY TO BAYNE MACHINE WO	NOT BE COPIED OR USED DETRIMENTALLY TO THE INTEREST OF BAYNE MACHINE WORKS, INC.		FOLERANCES: ED ±0.25 DEG 1.00 DEG	F	RIES SPEC	TL SERIES SPECIFICATIONS	
					MATERIAL				DRAWNBY CTT	DATE 10/22/2009	009 SCALE NONE	SHEET OF
					QTY FINISH			WEIGHT	CHECKED BY		DM	
											E H H	H300002/

		ш						ш						٥			4			υ						۵					4 A	REV	7
-		"L" DIM.	077	- <del>44</del>	07.7	ŧ	50°	c C L	Dc.	$50^{\circ}$	51°	51°	°C1	ç t	007	0	48°	48°	51°	51°	007	4.0	43°	48°	48°	48°	48°	RKS W	1605 - 864.288.3877		SHEET OF 4	ыко H3000027	
_	-	"K" DIM.		-8/5 cUT	"0/C 777	0/0	104 7/8"		Ø// /01	111"	104 7/8"	111 1/8"	"0" 1 2 1 1	21 0 1	"0/C UP P	0/0 611	113"	119 1/8"	112 3/4"	118 7/8"		7/1 // 1	123 3/8"	117 1/8"	123 1/8"	117 1/4"	123 3/8"		910 FORK SHOALS ROAD - GREENVILLE, SC 29605 - 864	FICATIONS	09 SCALE NONE	DWG NO H30	) - -
2		"J" DIM.		6U 3/8"	141 66 4 141	00 //	58 1/8"		0 1/4	64 3/8"	-28	64 1/4"	"1/2 03		10/3/2	0/0 + /	66 3/4"	"72 7/8"	65 7/8"	72 1/8"	110/2 02	12110	78 3/4"	71"	77 1/8"	"I <i>L</i>	77 1/8"	NF MACI	SHOALS ROAD -	TL SERIES SPECIFICATIONS	DATE 10/22/2009	/ DATE	7
_		"H" DIM.		38"	101 F 30	7/1 6.6	42 3/4"		0/C   +	40 1/2"	44 7/8"	42 5/8"	"Q/ 7 /Q"	01 10	"VI 7 2 C	4/1 CC	42 5/8"	40 1/4"	44 7/8"	42 5/8"	""" - C	5/ J/4	35 1/4"	42 1/2"	40 1/8"	44 5/8"	42 1/4"			F	DRAWNBY CTT	CHECKED BY	
e		"G" DIM.		20 3/8"	1.0 2 101	0// /	22 7/8"		213/4	20 5/8"	24 5/8"	22 3/8"	"01 00	211 02	10,101	0/1 01	23 3/8"	21"	24 5/8"	22 1/2"	10/ J UC	0/C N7	18"	23 1/2"	21 1/8"	25 3/8"	23"	ERWISE SPECIFIED VS ARE IN INCHES LEDANCES:	ACE DECIMAL ±015	ANGULAR TOLERANCES: NACHINED ±0.25 DEG BEND ±1.00 DEG		WEIGHT	e
_		"F" DIM.	ō			0/1 7	2 5/8"	ļ.	711 7	3 1/8"	3"	3 5/8"	"¢	N	"0/ F C	0/1 7	2 5/8"	3 1/8"	2 7/8"	3 1/2"		0/I 7	2 1/8"	2 5/8"	3"	2 7/8"	3 1/2"				_		_
4		"E" DIM.			"0" "0"	0/0 60	66 1/8"		00 1/4	70 1/8"	67 1/4"	71 1/4"	"11 52		"U" 1 22	711 11	73 7/8"	"87	74 3/8"	78 1/2"	1107 V 22	0/1 //	81 3/8"	77 3/4"	81 7/8"	"67	83"	CONFIDENTIAL	OLE PROPERTY OF ORKS, INC. AND IS IN TIME IT MILET	NOT BE COPIED OR USED DETRIMENTALLY TO THE INTEREST OF BAYNE MACHINE WORKS, INC.		Ŧ	4
Þ		"D" DIM.			E 0 1 /0"	0/1 00	55 1/4"	Ē	10	58 3/4"	56 3/8"	59 7/8"	RO E /0"		"0/ F F Z	04 1/0	60 3/8"	63 7/8"	60 5/8"	64 1/8"	10/ F C 3	0/1 CQ	66 5/8"	62 7/8"	66 3/8"	64 1/8"	67 5/8"		DRAWING IS THE SC BAYNE MACHINE W BECALLARLE AT AN	DETRIMENTALLY TO DETRIMENTALLY TO BAYNE MACHINE W	MATERIAL	QTY FINISH	-
		"C" DIM.	10, F U F	10 1/8"	1.6.1	0/1 01	16 1/8"		0/I 0I	16 1/8"	16 1/4"	16 1/4"	16.4 /0"	01 01	16.4 (01	0/1 01	16 1/8"	16 1/8"	16 1/8"	16 1/8"	10,101	0/I QI	16 1/8"	16 1/8"	16 1/8"	16 1/4"	16 1/4"						
ى ب		"B" DIM.	Ē	<i>\</i>	14	-	"11"	-		11"	13 7/8"	13 3/4"	۱۰Z		14	-	11"	"11"	13"	13"	14	,	۳7"	11"	11"	13 7/8"	13 3/4"						Ω
_	-	"A" DIM.			E.0. 1 (0)	20 1/2	50"		4/C   C	53 1/2"	50 1/4"	53 3/4"	۶۸"	5	E7 1 Mi	7/1 /0	54"	57 1/2"	54"	57 1/2"	Loui	0C	59 1/2"	56"	59 1/2"	56 1/4"	59 3/4"						
ø		PART #	1900-0186	1900-0027	1900-0187	1900-0261	1900-0121	1900-0274	1900-0275	1900-0188	1900-0043	1900-0189	1900-0277	1900-0029	1900-0278	1900-0263	1900-0116	1900-0270	1900-0045	1900-0271	1900-0279	1900-0031	1900-0265	1900-0140	1900-0272	1900-0177	1900-0273						Q
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		MODEL NUMBER	TL 1128 **	TL 2228 **	TL 1128 (TOP HOLES) **	TL 2228 (TOP HOLES) **	TL 2228-2524 **	TL 1128-2524 (MID HOLES) **	TL 2228-2524 (MID HOLES) **	TL 2228-2524 (TOP HOLES) **	TL 2228-2526 **	TL 2228-2526 (TOP HOLES) **	TL 1132 **	TL 2232 **	TL 1132 (TOP HOLES) **	TL 2232 (TOP HOLES) **	TL 2232-2524 **	TL 2232-2524 (TOP HOLES) **	TL 2232-2526 **	TL 2232-2526 (TOP HOLES) **	TL 1134 **	TL 2234 **	TL 2234 (TOP HOLES) **	TL 2234-2524 **	TL 2234-2524 (TOP HOLES) **	TL 2234-2526 **	TL 2234-2526 (TOP HOLES) **						8 7 1
	<u> </u>	ш						ш			I			۵			4			υ						۵					۷		


Page: 42 of 49









**Document Number:** 1900-0021 **Issue Date:** 04/22/13 **Revision No:** 006 **Page:** 45 of 49



ITEM       PART       ND.       DESCRIPTION       CTY         1       6083-1025       HAND       VALVE       - 1750       PSI       RELIEF       I         2       6083-1510       UNIVERSAL       C-HDDK       1       1         3       6083-1510       UNIVERSAL       C-HDDK       1         4       6083-1520       METRD/EATON       HANDLE       1         5       8810-0303       CDITER       PIN<(J/16" × 1/2")       2         6       6220-0806       ST       ADAPTER       (#6 JIC × #6 SAE)       2         7       6248-0006       #6 JIC CAP NUT       6       2         8       7601-0003       HAND VALVE       MUT       2         9       9001-0416       1/4-20 × 2" HHC.S.       2       2         10       9401-0400       1/4-20 × 2" HHC.S.       2       2         10       9401-0400       1/4-20 × 2" HHC.S.       2       2	6083-1020     05/24/07     CTT       6183-1020     05/24/07     CTT       610     8 8013-0303     05/24/07     CTT       20     8 24-006     05/15/99     CTT       06     8 244-006     05/15/99     CTT       00     9 27/97     04/17     CT	SINGLE HAND DWG. N VE W/BRACKET 600
		This short gis private and sominetrical amount intervent of Barnie Morks, Inc. Greenving, S.C. It MUST NOT be copied an lent intervention of EAVIN MARKS, INC., and must be somercy, et land with tender and/or completion of order to the purchasing department. Inc. Inc. consent of the MARKS, INC., and must be somercy, et land with tender and/or completion of order to the purchasing department. Inc. Inc. Inc. Inc. Inc. Inc. Inc. and must be somercy. Second of the order of the purchasing department. Inc. Sc. Stable Jarnie 1, 2000 = 1,520 - Aveluant ±0.250 - TER 06/07/96 BKB 06/11/96 VALV.
NJTE: 1. SEAL REPAIR KIT P/N + 3000-0385 2. HANDLE REPLACEMENT KIT P/N + 5083-1501		CONFIDENTIAL The afformation and confermation of the MADHIE MADHE WATHER WATHER WATHER WATHER WATHER WATHER AND A 1990 A







www.baynethinline.com

Customer Care: 800.535.2671

Fax: 256.585.6762

The Heil Co. 4301 Gault Avenue North Fort Payne, AL 35967